



## Addendum 1

SCC - Tyger River Campus BMW Parking Lot J

**Project Number:** H59-6297-JM-F

02/26/2024

- 1) The work shall be done between 4/26/2024 – 5/5/2024.
- 2) Paint stop bars and the word "STOP" at the end of each parking lane as needed.
- 3) The layout plan of the parking lot and marking of the placement of the light pole base must be provided prior to 4/4/2024. Coordinate with the Project Manager to deliver and discuss plan.
- 4) ADA spaces need to be painted compliant with ADA regulations. Placement of ADA signpost with a 2" channel post will be done with a base of at least 30" deep in a metal 6" pipe, backfilled and filled with concrete. Metal pipe will be at least 4 feet above ground, and painted safety yellow. Supply and install parking space signs.
- 5) Safety crosswalk will be painted white, 5 feet wide, with cross hatching every four feet at a 45-degree angle.
- 6) Quote date is unchanged. Quotes are due on Thursday 3/21/2024, at 2:00 pm.
- 7) All forms must be used as documented in previous communication.